


'Life at the Guild'_Elevation G

Worktop in 18mm MDF finished in 2 pack cellulose lacquer (colour TBC)

Existing 'Desk Case' free-issue from M-shed. MDF carcase to be decorated in conservation-grade paint finish to interior. Exterior in 2 pack cellulose lacquer to match worktop

32" touchscreen free-issue by M-Shed, installed on worktop. Media player and cables concealed in plinth below


875mm high x 12mm thick MDF panel with DTM graphic print to front face mounted to wall via aluminium split battens



'Life at the Guild' Plan 02

Front edge of worktop in welded 50x50 SHS. Powdercoat finish (colour TBC)

Existing deep red MDF wall to be redecorated in grey emulsion paint (colour TBC)



Clear wheelchair access below worktop

Existing 'Desk Case' free-issue from M-shed. MDF carcase to be decorated in conservation-grade paint finish to interior. Exterior in 2 pack cellulose lacquer to match worktop

Touchscreen mounted to worktop

Sketch Visual

General Notes: 01. Do not scale. 02. Verify all dimensions before commencing work. 03. Report all discrepancies or omissions. 04. All dimensions in millimetres unless stated otherwise.	Status: TENDER	Revisions:			Revisions:			Project A HISTORY OF PLACE M-SHED BRISTOL	Title 'LIFE AT THE GUILD' 02 DETAILS	Job No.	Scale	Date	Project East Design 1 York Road London E7 9HT Tel: 020 8503 0277 Mob: 07967 507660
		Rev	Date	Description	Rev	Date	Description			148	1:20@A3	16.07.17	
										Drawing No.		Rev	
										148_209		/	